



Product Quality Summary Report

Naples Monthly QC Summary

Example Report

Plant: **Naples Golden Gate Quarry**

Mine no.: **03-616**

	# 67 Stone FDOT Code 41 / 12	# 57 Stone FDOT Code 10	S-1-B 89 Stone FDOT Code 52	Screenings FDOT Code 20	#5 Stone 3/4" Drainfield	#9 Stone	Limerock Base		
1 1/2"(37.5)					100				
1"(25)	100	100.0			96		3 1/2"		100
3/4"(19)	98	90			43		#4 (4.75)		45
1/2"(12.5)	54	35	100.0		10		LBR		150
3/8"(9.5)	30	7	95	100.0	8	100	Optimum Moisture		9.0
#4(4.75)	6	2	36	100.0	5	85	Dry Density (lbs/ft³)		125.0
#8(2.36)	2	2	4	89	5	10			
#10(2.0)									
#16(1.18)			1	67		5			
#30(0.06)			1	50		4			
#40(0.425)									
#50(0.30)				33		3			
#80(0.18)									
#100(0.15)				11					
#200(0.075)	0.54	0.34	0.36	2.28		0.68			
LA Abrasion B	39	34							
LA Abrasion C			35						
LA Abrasion D						35			
SPGR (Dry)	2.385	2.369	2.385	2.477		2.407			
SPGR (SSD)	2.462	2.446	2.471	2.549		2.478			
SPGR (Apparent)	2.585	2.574	2.593	2.669		5.591			
Absorbtion	3	3	3	3		3			
FM	6.64	6.95	5.61	2.43		3.93			

Rip Rap
6 in.-12 in.

Rip Rap
12 in.-24 in.

Rip Rap
24 in.-36 in.

Rip Rap
36 in + Bolders

Fill Material
White Fill
Screened Fill
Rough Fill